Institute of Commissioning & Assurance (ICxA)

Gate Review Crosswalk

Canada: Guide to Project Gating

Version 0.1, November 2026

The Treasury Board of Canada Secretariat's Guide to Project Gating sets out a gating model for federal projects. Gate 4, Confirm readiness for service, checks that the project is complete enough to move into operational use and that the business owner accepts responsibility.

The review comes late. By the time it is held, systems have been tested or not, the operating organization has been recruited and trained or not, and procedures have been written or not. A review team can report what is missing, but there is little time left to fix it. The ICxA readiness criteria describe the evidence that answers the gate's question, and most of that evidence can be examined long before the last gate.

What readiness covers

Readiness is the condition in which sufficient evidence is available for a decision to proceed (ICXA-10001 cl. 8.1). It applies at every point of commitment in a project, not only at the end: readiness to commit, to proceed, to integrate and to operate. It covers the asset and its systems, which must be designed, procured, built, tested and integrated so that each system works with the others. It covers the organization that will operate the asset: its people, its organization, its care of the asset, and its systems and processes. It also covers the interfaces and contracts between the parties, and the evidence and governance on which each decision rests.

What can be checked before the last gate

Stage	What the evidence shows	Criteria
At the investment decision and through engineering: the path	Operating outcomes are defined. Stage-gates, criteria and evidence needs are set in advance. Roles and independence are assigned. A systems completion strategy and an operational readiness plan exist.	A01, A02, A04, B01, B03, C01, C02, D01, E01
During procurement and construction: the progression	Readiness is in the master schedule. Interfaces and vendor deliverables are tracked. Systems are being completed by system. People, organization, asset and systems capability are developing on time. Reviews are held and recorded.	A03, B02, B04, C03, C04, D02, D03, D04, D05, E02, E04, F01, F03
From commissioning to operations: the condition	Testing is prepared and complete for each system, and systems work together. Deficiencies and deferred work are controlled. Transfer follows a recorded review and acceptance. Ramp-up is monitored.	C05, C06, D06, E03, F02, F04

The grouping is ICxA guidance. Each project defines its own stage-gates and readiness conditions under the ICxA Standards, so the timing on a given project follows what that project has defined. The 28 criteria are set out in full in the ICxA Readiness Audit Criteria, at icxa.net/readiness-audit-criteria.

Gates and the ICxA criteria

Source: Guide to Project Gating, Treasury Board of Canada Secretariat.

Gate and what it confirms	Related ICxA criteria	Earliest stage the evidence exists
Gate 4, Confirm readiness for service: testing, training and user documentation are in place, and the business owner accepts responsibility	B03, C05, D02, D05, D06	The path
Gate 5, Complete project and conduct post-implementation review: deliverables are handed over to operations and accountabilities are confirmed	D06, F03, F04	The condition

How to read this crosswalk

The mapping is ICxA's reading of the published gate document, made at the level of review area. It has not been reviewed or endorsed by the body that owns the gate, whose own guidance governs how its reviews are run. ICxA welcomes correction from the gate owner and will prepare a mapping to individual review questions on request.

The crosswalk does not replace a gate review. It shows what a review team, a sponsor or a delivery body can ask to see earlier, so that the final review confirms a condition that has been building and does not discover one that is missing.

Terms of use

Public bodies acting in an oversight role, including audit offices, regulators, parliamentary committees and government project assurance bodies, may use, cite and reproduce this crosswalk without charge and without ICxA membership. Please attribute it to the Institute of Commissioning & Assurance and state the version used. An altered version should not be presented as ICxA's. Use of this material does not mean that ICxA has reviewed or endorsed a body's findings.

ICxA membership is required to state publicly that an organization, service or assessment is aligned with the ICxA Standards, to hold ICxA credentials, and to use this material in a commercial service.

The ICxA Standards are available in full, free of charge, through the Corporate Preview membership. More at icxa.net.